



NOTE "A"

The subdivision of the N.W. 1/4 of the N.W. 1/4 of Section 30 by Tamblin in 1935 showed the North & South lines of said subdivision being 1373.7 feet in length. The axel found at the N.E. corner of said subdivision is probably in accordance to that 1935 survey, but when I proportioned that quarter in relation to the original survey in 1861, my point falls 43.22 feet west of the axel. I conclude that Tamblin's survey is grossly in error as far as it being the N.W. 1/4 of the N.W. 1/4 of said Section 30 as noted on his map.

REGISTERED PROFESSIONAL LAND SURVEYOR
G. Dennis Edwards
 OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

SURVEY FOR: GENE SMITH & MIKE REED

LOCATION: NW 1/4, SEC. 30, T5N, R27 E., W.M. MORROW COUNTY, OREGON

DATE: 5-19-80 SCALE: 1"=400'

● MONUMENTS FOUND (000) OF RECORD

○ 5/8" IRON RODS SET JOB NO. S8005083

EDWARDS SURVEYING P.O. BOX 763
567-3336 HERMISTON, OREGON