



Section 36, T5N, R26E, W.M.
1" = 1000'

- denotes original concrete monument found, a 1 1/2 in. x 30 in. iron pipe with a 2 1/2 in. Brass Cap set
- ⊙ denotes Brass Cap found as set by G.L.O. in 1939
- denotes 1 1/2 in. x 30 in. iron pipe with a 2 1/2 in. Brass Cap set
- denotes 5/8 in. x 30 in. iron pin with aluminum cap set

NARRATIVE

The purpose of this survey was to breakout three parcels from the Northeast one-quarter of the Northwest one-quarter and the North half of the Northeast one-quarter of Section 36, Township 5 North, Range 26 East, W.M.

Our firm originally broke down Section 36 in a survey for Sam Woolsey, dated March 23, 1977, Morrow County Survey Records drawing no. C-85-K. Subsequent to that we found that the point we had been using for the Northwest corner of Section 36 was incorrect. Research by McCullough-Bryant, Inc., under contract to the Corps of Engineers, has shown that original concrete monuments set by Worthington in 1906, which are shown on plats filed by Tamblyn in 1935 should be used to control Section 25 and subsequently, the North line of Section 36. We found those as shown on the drawing and corners on the South line of Section 36 which are 1939 G.L.D. markers to breakdown the Section.

Therefore, the survey for Sam Woolsey, dated March 23, 1977 is incorrect and this survey shall supercede it.

Bearings are based on a survey for Morrow County by Krumbein Engineering, Ltd., dated May 8, 1980, Morrow County Survey Records drawing no. D-303-K.

Morrow County Survey
Date November 22, 1982
Revised By m. Hughes
No. C-514-K
David H. Klein
OREGON
JULY 17, 1982
DAVID H. KRUMBEIN
333

KRUMBEIN ENGINEERING CO. ENGINEERS - SURVEYORS - PLANNERS 221 S. Main, Pendleton, Oregon	SCALE 1" = 200'
	DATE June 8, 1982
Survey for TOLLESON ESTATES	DRN. BY KRH
located in Section 36, T5N, R26E, W.M.	CKD. BY HAI
	DRNG. NO. 82-19C

C-514-K-