



NARRATIVE:

The purpose of this survey is to partition a 172 acres ± parcel into two pieces along a line defined by the property We tied to the Plat of "Ployhar Estates" and those points shown as found. This drawing also shows a previous partition done in 1979, County Surveyor No C-221-K. The Southwest parcel of 120 acres is defined by the Deed provided to us and recorded in the Morrow County Deed Records M-21820. This parcel has not been surveyed and the bearings and distances are from the Deed. Bearings shown are true and are based on the Plat of "Ployhar Estates".

- denotes 3/8" x 30" iron pin with alum cap stamped PL 6 933 set
- denotes 3/8" iron pin with alum cap found

CURVE DATA				
No	Radius	Arc	Chord	Ch Bearing
1	2042.18	348.88	348.54	S65°41'00"W
2	1004.15	177.18	176.95	N65°50'34"E
3	1004.15	22.21	22.21	N71°31'54"E
4	1160.51	298.35	297.58	S64°47'55"W
5	322.40	147.38	146.10	N44°20'10"E
6	512.78	139.04	138.61	N59°00'28"E

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=300'	Drn. By MLD	Drng. No. 53-29	Revision 1
	Date 7-22-83	Ckd. By D.H.K.	Job No. 83-74	Revision 2
Survey for JACK PLOYHAR T23, R26E		7-26-83 MLD C-629-K		

C-129 K