



- denotes Brass Cap found
- denotes monument found as noted
- ◐ denotes 3/8" iron pin over conc. mon. find
- () denotes record bearings & distances
- denotes 3/8" iron pin w/alum. cap set
- ▲ denotes Brass Screw & Washer set

- ① Forth & Idaho, found 1915 G.L.O. Brass Cap.
- ② Forth & Oregon, found PK nail bottom of concrete ditch as shown on County Surveyor Drwg No. 303K.
- ③ Forth & Washington, set 3/8" iron pin with aluminum cap.
- ④ W 1/4 Sec 24, found 1915 G.L.O. Brass Cap, N 76° 56' 32" E, 19.33' from proportion cor., set 3/8" pin w/alum Cap as shown
- ⑤ Found original concrete monument.
- ⑥ Third & Washington, found original concrete monument, set 3/8" iron pin with Brass Cap over monument.
- ⑦ Third & Oregon, set 3/8" iron pin with aluminum cap, using original angles and distances.
- ⑧ Third & Idaho, found 3/8" iron pin over original concrete monument.
- ⑨ Second & Idaho, found 1915 G.L.O. Brass Cap, also found 3/8" iron pin over original monument as shown in detail.
- ⑩ Second & Oregon, found 3/8" iron pin by Telek Co. Drwg. No. 2-223-K. Set 3/8" iron pin in original position, as shown in detail.
- ⑪ C 1/4 Sec 24, computed location using original angles and distances.
- ⑫ Found original concrete monument.
- ⑬ First & Washington, found original concrete monument. Fnd. Brass Screw & Washer, as shown in detail.
- ⑭ First & Oregon, found 3/8" iron pin, set 3/8" iron pin with aluminum cap in original position, as shown in detail.
- ⑮ First & Idaho, found 1915 G.L.O. Brass Cap.
- ⑯ Division & Idaho, found 1915 G.L.O. Brass Cap.
- ⑰ Division & Oregon, set 3/8" iron pin, in computed location using original angles and distances.
- ⑱ Found Brass Cap M.C. No. 3133-5, original corner falls in river. N 40° 13' 07" E - 19.76' to computed location.

Concrete Monuments are those shown on H. Tamblin's plat of Irving Washington's original 1906 survey. Jan. 1932 DHK made corrections.

622
D-722-K

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=200'	Drn. By R.D.J.	Drwg. No. 63-160	Revision 1 1-92
	Date 6-13-83	Chk. By D.H.K.	Job No. 83-15	Revision 2
Survey for MORROW COUNTY SURVEYOR				
6 1/2 Sec. 24, T5N, R26E, W4M				