

WEST 1/4 COR SEC. 16. FND R/R SPIKE

E WILSON RD.

30.00

30.00

S 89° 15' 30" W PER KRUMBEIN SURVEY FOR MORROW COUNTY DATED 7-12-83

FND ALUMINUM CAP MKD PLS 933

40.0

208.71

ROAD EASEMENT

N 89° 15' 30" E 100.00



SAM BOARDMAN GRADE SCHOOL PROP.

WEST LINE OF SEC. 16 NO° 26' 28" W BEARING BASE

BOARDMAN LATCH KEY 0.5 ACRES

218.00

S 0° 26' 28" E 218.00

S 89° 15' 30" W 100.00

- DENOTES MON. FND. AS NOTED
- DENOTES 5/8" X 30" REBAR WITH PLASTIC CAP MKD LS 1861 SET

NARRATIVE

THE INTENT OF THIS SURVEY IS TO CREATE A 100.00 WIDE BY 218.00 PARCEL 208.71 SOUTH OF THE E OF WILSON RD. & ALONG THE WEST LINE OF SEC. 16. KRUMBEIN'S 7-12-83 SURVEY WAS HELD FOR THE E OF WILSON RD. & HIS 2-1-1978 SURVEY # 296-K WAS HELD FOR THE WEST LINE OF SEC. 16.

R & M SURVEYORS & CONSULTANTS INC. 922-3093
 P.O. BOX 709, IRRIGON, OR. 97844

PART OF TAX LOT 401, SEC. 16, T. 4 N., R. 25 E. W.M. MORROW CO. OREGON.

REGISTERED PROFESSIONAL LAND SURVEYOR

Earl D. Ming

OREGON
 JUL 14, 1979
 EARL D. MING
 1881

RECEIVED BY
 Morrow County Surveyor
 Date 11-28-86
 Rec'd By DMH
 No. A-844K
A-908-K-679

DATE: 10-15-86
 DRWN BY: EDM
 CHK'D BY: KJM
 SCALE: 1" = 50'

FND 5/8" IRON ROD SEC OF SCHOOL PROP. HELD FOR LINE