

SURVEY FOR EARL CRISMON
 IN SE 1/4 SEC. 27, T2S, R26E, W.M.,
 IN "RIVERSIDE ADD." TO City of Heppner,
 MORROW COUNTY, OREGON
 5/18/89 Job # SB905029
 EDWARDS SURVEYING, P.O. Box 763
 567-3336 HERMISTON, OREGON

SCALE: 1" = 30'

- MONUMENTS FOUND
- 1/2" x 24" Rebar set with Alum. tag # 951
- (000) OF RECORD plat of RIVERSIDE ADD

NARRATIVE: The purpose of this survey is to partition Lot 9, RIVERSIDE ADD to Heppner into two parcels for the pending sale of the two houses that sit on it. I put the dividing line 2' westerly of an existing fence so that there would be room to get south of the garage on the west parcel. I assumed the 1/2" Iron Pipe at the north cor. of lot 9 was from the original survey of RIVERSIDE ADD. by Tambllyn. I used monuments at cor of Riverside Ave & Shobe Streets & on the North line of Lot 14 because the fit well for line & distance

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 15, 1971
 G. DENNIS EDWARDS
 951

Find 1/8" Iron Rod
 ORIG. UNKNOWN
 @ Lot 14 as shown
 on Tax map.

RECEIVED BY
 Morrow County Surveyor
 Date 12/89
 Rec'd By *DE*
 No. B-895-E

