


Ferguson Surveying



MT. VERNON, OREGON
PHONE (503)932-4520
FAX (503)932-4430

MONUMENTATION AND MAINTENANCE

See standard U.S.F.S. "INDEX No." in the circle on the map. Monuments are stamped as shown below. On each Bearing tree, nailed a brass washer stamped "PLS 848" blaze above the BT scribe and nailed warning signs on the back. Set steel posts with warning and boundary signs, on line within 5 ft. of property corners, or a single post with a warning sign within 5 ft. of controlling corners.

See "CERTIFIED RECORD OF LAND CORNER MONUMENTATION" forms on file in the office of the Morrow County Surveyor for a complete history, description of evidence found, monument set, and accessories established at all corners set or maintained.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

(E-1) T5S
R27E R28E
S 1 | S 6
S12 | S 7
1936
(GLO BRASS CAP)

Ponderosa Pine, 28" dia., bears N46°15'W, 60.8 ft., scribed: T5S R27E S1 BT
White Fir, 8" dia., bears S79°30'E, 38.6 ft., scribed: T5S R27E S7 BT
Douglas Fir, 26" dia., bears S49°15'W, 241.4 ft., scribed: T5S R27E S12 BT

(G-1) W C
T5S
R27E R28E
1/4
S12 | S 7
1992
PLS 848

Douglas Fir, 12" dia., bears N17°15'W, 39.8 ft., scribed: 1/4 S12 BT
Douglas Fir, 12" dia., bears N46°30'E, 55.6 ft., scribed: 1/4 S 7 BT
Douglas Fir, 12" dia., bears S16°15'W, 30.5 ft., scribed: 1/4 S12 BT

(E-2) T5S R28E
S6
W1/16
S7
1992
PLS 848

Ponderosa Pine, 30" dia., bears N11°11'E, 302.6 ft., scribed: W1/16 S6 BT
Ponderosa Pine, 12" dia., bears S55°46'W, 91.9 ft., scribed: W1/16 S7 BT

(G-3) T5S R28E
C1/4
S7
1992
PLS 848

Ponderosa Pine, 24" dia., bears N08°02'E, 57.0 ft., scribed: C1/4 S7 BT
White Fir, 12" dia., bears S82°22'E, 51.2 ft., scribed: C1/4 S7 BT
Red Fir, 16" dia., bears S49°56'E, 39.3 ft., scribed: C1/4 S7 BT
White Fir, 16" dia., bears S45°03'W, 31.7 ft., scribed: C1/4 S7 BT

(E-3) T5S R28E
S6
1/4
S7
1992
PLS 848

Douglas Fir, 20" dia., bears N57°30'E, 55.4 ft., scribed: 1/4 S6 BT
Douglas Fir, 16" dia., bears S21°30'E, 40.1 ft., scribed: 1/4 S7 BT
Douglas Fir, 14" dia., bears S48°15'W, 31.8 ft., scribed: 1/4 S7 BT

(G-5) T5S R28E
1/4
S7 | S8
1938
(GLO Brass Cap)

Western Larch, 24" dia., bears N83°30'E, 28.4 ft., scribed: 1/4 S8 BT
White Fir, 12" dia., bears S89°15'W, 33.9 ft., scribed: 1/4 S7 BT

(E.25-1) T5S
R27E R28E
Line Tree
WC
S12 | S 7
1992
PLS 848

Ponderosa Pine, 24" Dia., bears N34°45'W, 138.2 ft., scribed: LT S12 BT
Douglas Fir, 10" Dia., bears N73°30'E, 49.0 ft., scribed: LT S 7 BT

(G.5-1) T5S
R27E R28E
Line Tree
WC
S12 | S7
1992
PLS 848

A Douglas Fir, 14" dia., bears S55°45'W, 37.2 ft., scribed: LT S12 BT
A Yew, 7" dia., bears S64°30'E, 68.1 ft., scribed: LT S 7 BT

(F-2) T5S R28E
NW 1/16
S7
1992
PLS 848

Ponderosa Pine, 14" dia., bears S80°51'W, 37.2 ft., scribed: NW 1/16 S7 BT
Ponderosa Pine, 16" dia., bears N18°22'E, 28.8 ft., scribed: NW 1/16 S7 BT

(J-3) T5S R28E
S7
1/4
S18
1939
(GLO Brass Cap)

White Fir, 8" dia., bears N33°15'E, 57.0 ft., scribed: 1/4 S7 BT
Douglas Fir, 28" dia., bears S67°45'E, 37.5 ft., scribed: 1/4 S18 BT
Douglas Fir, 20" dia., bears S41°30'W, 36.7 ft., scribed: 1/4 S18 BT

(F-3) T5S R28E
C
N1/16 | S 7
C
1992
PLS 848

Douglas Fir, 10" dia., bears N67°27'W, 48.0 ft., scribed: C-N 1/16 S7 BT
Ponderosa Pine, 24" dia., bears N69°55'E, 62.6 ft., scribed: C-N 1/16 S7 BT

RECEIVED BY
Morrow County Surveyor
Date 7/9/92
Rec'd by [Signature]
No. C-938-E

707-C