



Scale: 1" = 200'

**NARRATIVE:**

The purpose of this survey is to stake the South Half of the SW 1/4, SW 1/4 of Section 17, T4N, R25E, W.M., so a fence can be built along the North line.

I am in the process of remonumenting Section 17 for the County, and this survey is based on my survey, which is not filed yet.

I believe the RR spikes near the SW corner and S 1/4 corner were set by Tuers in a 1977 Dependent Resurvey but I did not use them because they do not fit apparent property lines or the original G.L.O. survey of 1869 by Thompson. This is also true of the S 1/4 corner of Section 18. See my County Remonumentation Survey of Section 13, T4N, R24E and Sections 17 & 18, T4N, R25E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

G. Dennis Edwards

OREGON  
JULY 11, 1971  
G. DENNIS EDWARDS  
951

**LEGEND:**

- Found monuments, as noted.
- Set 5/8" x 30" rebar with plastic cap #951.
- (000) of Record. Tuers' Dependent Resurvey, unless noted Jones 1918, G.L.O. Survey.
- [000] of Record. Original G.L.O. Survey, Contract #131, 1869 by Thompson.

RECEIVED BY  
Morrow County Surveyor  
Date 10/93  
Rec'd By SKB  
No. C-967-E (739)

Survey for LEE DOCKEN  
In SW 1/4, SW 1/4 Section 17, T4N, R25E, W.M.,  
Morrow County, Oregon  
2/25/93 Job #S9302008  
Edwards Surveying P.O. Box 763  
567-3336 Hermiston, Oregon 97838