



LEGEND:

- Found monument as noted. Hayes 1965 Sur. for Boeing Co.
- ⊙ Set 1" x 30" Iron Pipe with 2 3/8" Brass Cap.
- (000) of Record. Original Survey Contract #122 by Thompson in 1867.
- [000] of Record. Hayes survey for Boeing Company in 1965.

RECEIVED BY

Morrow County Surveyor
 Date 1/19/95
 Rec'd By SKB
 No. B-1034-E (807)

NARRATIVE:

The purpose of this survey is to stake and describe an area enclosed by a fence which contains a Kiosk so it can be deeded to Morrow County. All original monuments along Immigrant Road have been obliterated. To establish the North corners of Section 29 I used the centerline of Immigrant Road for Northings and proportional distances for Eastings from the found Northwest corner of Section 30 and the Road intersection at the North Quarter corner of Section 28. These corners were confirmed by measurements South to the South Quarter corner of Section 28 and South to the West Quarter corner of Section 30.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

J. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951
 REISSUE 12/31/95

Survey for **MORROW COUNTY & CHARLIE DOHERTY**
 In NE 1/4 Section 29, T2N, R25E, W. M.,
 Morrow County, Oregon
 1/12/95 Job #59412144
 Edwards Surveying P.O. Box 763
 503-567-3336 Hermiston, Oregon 97838