

18 Found Stone  
19

4818.75

N0°03'56"W  
5333.10

19 20  
30 29  
Found Stone  
in Mound.

(S89°39'E)  
40.00 CHAINS  
N89°05'03"E  
2670.27

Corner not found

(S89°39'E)  
40.11 CHAINS  
N89°05'03"E  
2569.55

T5S

19 30  
24 Found Stone  
in Mound  
25

35.48 ACRES  
**ANSON WRIGHT PARK**

HIGHWAY RIGHT OF WAY

40' 75'  
50' 75'

OREGON STATE HIGHWAY 207

2705.29

2582.32

30 Found Stone  
and B.I.  
31

N1°17'07"W  
5287.61

Narrative:

The purpose of this survey was to establish the western boundary of those parcels belonging to Morrow County for Anson-Wright Park. This property was obtained from the Wrights and Kinzua Corporation.

The land lies East of the North-South centerlines of Sections 19 and 30 and West of State Highway 207.

The South 1/4 of section 30, the NE and NW corners of section 30, and the north 1/4 of section 19 were found. The north 1/4 of section 30 was not found and was repositioned on line between the NE and NW corners of section 30 using the call from the thread of the stream of Rock Creek (56'W) as stated in the original GLO notes.

In 1986, PLS 933 made a survey of this park ( Morrow County Survey D-860-k-660 ) and set pins on the Highway Centerline North and South of the park. These pins were not based on corners establishing the North-South centerlines of sections 19 and 30. Therefore, I made no attempt to find and tie these pins.

Basis of Bearings

Bearings were determined by first determining the Oregon State Plane Coordinate (NAD83) for all the corners. Grid bearings and distances were determined from these coordinates. The bearings were rotated 0°37'08" clockwise to give the bearings shown on this plat. The grid distances were multiplied by 1.000294841475 to give the distances shown on this plat.

NOTE:

A complete description of found corner evidence and monumentation may be found in the Certified Record of Land Corner Monumentation forms filed with this plat.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 12, 1969  
DAVID L. HADDOCK  
#52

LEGEND




SET 2 1/2" BRASS CAP  
IN CONCRETE



SET 5/8"X18" REBAR  
WITH 2" AL CAP



SET 2 1/2" AL CAP  
ON 30" AL PIPE



HIGHWAY RIGHT OF WAY



POSTED PROPERTY LINE



HIGHWAY CENTERLINE

(S89°39'E)

RECORD BEARING

N89°05'03"E

OBSERVED BEARING

40.11 Chains

RECORD DISTANCE

2569.55

OBSERVED DISTANCE

DAVID L. HADDOCK, SURVEYOR and ENGINEER  
P.O. Box 1574 (503) 276-2174  
Pendleton, OR. 97801-0450

I hereby certify that this map is an accurate representation of a survey made under my direct supervision during February of 1995.

ANSON WRIGHT PARK SURVEY

For Morrow County Dept. of Public Works  
% Duck Lusher, Assistant Director  
(503) 989-8211  
P.O. Box 453  
Lexington, OR. 97839

1/4 SEC. 19 & 30, T 5S, R 26E, W. 4., MORROW CO., OR

Survey Performed With

WILD GPS SYSTEM 200  
WILD T2E THEODOLITE  
WILD DI 1000 DISTOMAT

377-95  
SK B  
L-1032-E (P)