


NOTES

- BEARINGS ARE BASED ON POLARIS OBSERVATIONS FROM CONTROL POINT A-3 WHICH IS N0°05'30"E, 355' FROM THE EAST ONE-QUARTER CORNER OF SECTION 12, T.6S., R.26E., W.M.
 - FOR ADDITIONAL INFORMATION ON CORNERS MONUMENTED OR REMONUMENTED, SEE THE 'CERTIFIED RECORD OF LAND CORNER MONUMENTATION' FORMS FILED HERewith.
 - FIELD BOOK REFERENCE - TRAVERSE BOOKS 2 AND 3 AND MONUMENTATION AND POLARIS OBSERVATION BOOK 4 OF THE INDIAN 1987 CADASTRAL SURVEY.

HISTORY

- ED SANDERSON, UNDER G.L.O. CONTRACT NO. 368 DATED SEPT. 7, 1880 SURVEYED THE TOWNSHIP LINE BETWEEN T.6S., R.26E. AND R.27E., W.M. HE ALSO SUBDIVIDED T.6S., R.26E. UNDER G.L.O. CONTRACT NO. 368 DATED SEPT. 7, 1880.
 - THE B.L.M. REMONUMENTED THE SOUTHWEST AND NORTHEAST SECTION CORNERS AND THE EAST AND WEST ONE-QUARTER CORNERS OF SECTION 12, T.6S., R.26E., W.M. IN 1982.



NARRATIVE

THIS SURVEY WAS PERFORMED AT USDA FOREST REQUEST DURING AUGUST AND SEPTEMBER OF 1987. THE PURPOSE OF THE SURVEY WAS TO REMONUMENT THE SECTION AND ONE-QUARTER CORNERS, SET THE CENTER ONE-QUARTER AND THE ONE-SIXTEENTH CORNERS NECESSARY TO POST THE BOUNDARIES OF NATIONAL FOREST SYSTEM LANDS IN SECTION 12 OF T.6S., R.26E., W.M. IN MORROW COUNTY, OREGON.

ALL FOUR SECTION AND ONE-QUARTER CORNERS NOT PREVIOUSLY REMONUMENTED BY THE B.L.M., WERE REMONUMENTED FROM EXISTING EVIDENCE IN THE FORM OF MONUMENTS AND BEARING TREES. THESE MONUMENTS AND THE B.L.M. BRASS CAPS WERE USED AS CONTROL POINTS IN A CLOSED TRAVERSE SURVEY USING A WILD T2E THEODOLITE AND A WILD DI-10 INFRA-RED EDM. THIS SURVEY IS DEPICTED ON THE SURVEY CONTROL DIAGRAM. THE CENTER ONE-QUARTER AND ONE-SIXTEENTH CORNERS WERE SET ON THE BASIS OF THIS SURVEY AND INSTRUCTIONS IN THE B.L.M. MANUAL OF SURVEYING INSTRUCTIONS-1973 AND CONTRACT SPECIFICATIONS. THE BOUNDARIES OF NATIONAL FOREST SYSTEM LANDS WERE POSTED WITH 6' STEEL POSTS AND FOREST SERVICE BOUNDARY SIGNS.

SURVEYOR'S CERTIFICATION

I, DAVID L. HADDOCK, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON, HEREBY CERTIFY, THAT THIS PLAT, AND THE NOTES HEREON, OR ATTACHED, ARE A CORRECT REPRESENTATION OF A SURVEY PERFORMED UNDER MY DIRECT SUPERVISION DURING THE MONTHS OF AUGUST AND SEPTEMBER OF 1987, AT THE REQUEST OF THE USDA FOREST SERVICE, IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON AND WITH THE ARTICLES OF THIS CONTRACT.

David L. Haddock

DAVID L. HADDOCK
OREGON LICENSE NO. 852

REGISTERED PROFESSIONAL LAND SURVEYOR

David L. Haddock

OREGON JULY 12, 1988
DAVID L. HADDOCK 852

RECEIVED BY
Morrow County Surveyor

Date: 2-7-2013

By: S.K.H

No.: 2013-178

Folder No.: 1072

LEGEND

- - FOUND BUREAU OF LAND MANAGEMENT (B.L.M.) BRASS CAP
- - SET 2" I.D. GALVANIZED IRON PIPE 30" LONG WITH 2 1/2" BRASS CAP FROM EXISTING EVIDENCE.
- - SET 2" I.D. GALVANIZED IRON PIPE 30" LONG WITH 2 1/2" BRASS CAP BY SURVEY.
- BOUNDARY OF NATIONAL FOREST SYSTEM LANDS POSTED.
- - - FENCE WITH POSSIBLE ENCROACHMENT.
- == ROAD INTERSECTING POSTED BOUNDARY OR SURVEY LINE
- N89°30'W, 40.30(2659.80)' - G.L.O. RECORD BEARING WITH DISTANCE IN CHAINS AND FEET.
- N89°16'42"W, 841.49(2760.80)' - SURVEY BEARING WITH DISTANCE IN METERS AND FEET.

TOWNSHIP 6 SOUTH, RANGE 26 EAST
 WILLAMETTE MERIDIAN
 SUBDIVISION OF SECTION 12
 INDIAN 1987 CADASTRAL SURVEY
 MORROW COUNTY, OREGON
 UMATILLA NATIONAL FOREST
 CONTRACT NO. 53-04R3-7-38

EXAMINED AND ACCEPTED FOR THE U.S. FOREST SERVICE
 THIS 19TH DAY OF OCTOBER, 1987.
 Dennis L. Gaylord C.O.R.
 I CERTIFY THAT THIS SURVEY WAS PERFORMED AT THE REQUEST OF THE UMATILLA NATIONAL FOREST.
 James A. Lawrence NATIONAL FOREST SUPERVISOR 10-19-87 DATE