

At the quarter section corner between sections 24 & 25 T₄ S. R.
25 E. N. M.

Dug and found remains of charred stake - charcoal showing
very plainly.

Renewed this corner by setting a rock 12x10x6 marked C. S. over a de-
posit of charred stone coal two feet below the surface. Made four
references or witnesses to this corner of four deposits of charred
stone coal 2 in. in diam. and from surface down 30 inches at a
distance of 10 lks. from the corner N. E. N. W. S. W & S. E.

October 23rd - 1909.

D. W. J. Reid

County Surveyor.