

Folder 1080, Date 10-1909

Book: 1, Page: 2023A

October 23rd 1909.

D. W. F. Reid

County Surveyor.

At the quarter section corner on the east line of section 25th T. 1 S.
R. 25th E. N. 2 M.

Found the government rock 20x8x4 in. marked $\frac{1}{4}$ lying on ^{the ground} the top of λ

Folder 1080, Date 10-1909
Book: 1, Page: 20 & 3A

having been removed from its original setting. Nothing therefore remains in the ground or on the surface by which to relocate this corner. I therefore go north to known corner on E. side of sec. 24 T₁P. 1 S. R. 25 E. N. M. being the quarter sec. cor. From thence I run South 80 ch., set temporary 1/4 cor. and run on south. At 120 ch. 10 lks. intersect E+W. line at sec. corner.

Return to temp 1/4 cor E. side Sec. 25 and set it S. ($\frac{2}{3}$ 10 lks) $6\frac{2}{3}$ lks. for the true quarter section corner on the E. line said sec. 25.

Dug hole 20 in. deep, made a deposit of charred stone coal, cut C. S. on the government 1/4 rock and reset it over the charred stone coal deep to the surface, set a rock 10 X 10 X 8 over it and raised a mound and made four witnesses of four deposits of charred stone coal 2 in. in diam. and from the surface down 30 inches at a distance of 10 lks from the cor. N. E. N. M. S. M. + S. E. for the quarter section corner on the E. line of sec. 25 T₁P. 1 S. R. 25 E.

October 23rd - 1909.

D. V. F. Reid
County Surveyor.