

Commencing at the corner to secs. 1, 2, 11+12, T<sub>4</sub>P. 2 S. R. 28 E. N. W. ✓  
 which is a rock firmly set in the ground having 1 notch on the E. side +  
 and one notch on the N. side and being 20 ft. N. of wagon track in the County  
 road and N.  $41^{\circ}10'$  E. from Vincents house, run thence south, 40.06  
 ch. a mound and mound of rocks in which the government rock had  
 been set for the quarter section corner bet secs 11+12 T<sub>4</sub>P. 2 S. R. 28 E.  
 but the rock having  $\frac{1}{4}$  on it, lying on surface of ground had been re-  
 moved from its original setting. Therefore ran south and at 80.10  
 ch. intersected the corner to secs. 11, 12, 13 + 14 said T<sub>4</sub>P. Returned to  
 the  $\frac{1}{4}$  cor bet. secs 11+12 said T<sub>4</sub>P. and reset the original  $\frac{1}{4}$  rock  
 in the mound over a deposit of charcoal 30 in. deep. Made four ref-  
 erences or witnesses of charcoal 2 in in diam. and from surface down  
 30 in. at a distance of 10 lks. from the corner N. E. N. W. S. W. + S. E.

Mar. 21<sup>st</sup> 1910

D. W. F. Reid

County Surveyor

At the S. W. cor Sec. 28 or the cor. to secs. 28, 29, 31 + 32 T<sub>4</sub>P. 4 N. 23 E. N. W. ✓