

From the quarter section corner on the west side of section 31 T<sup>h</sup>. 4 N. Range 23 E. I run south and at 40.00 ch. set temp. stake and continue south. At 80.22 find  $\frac{1}{4}$  sec. cor on west side sec. 6 T<sup>h</sup>. 3 N. R. 23 E. Returning to the temporary stake at S.W. cor sec. 31 - T<sup>h</sup>. 4 N. R. 23 E. set it south 11 links and run east. At 81.70 intersect N + S. line 20 lks south of corner which is marked by a mound and four pits. To mark this corner more permanently I drive a bolt (iron) 8 in x  $\frac{7}{8}$  in W. pit and a bolt 18 x  $\frac{7}{8}$  in. in E. pit and set a rock 24 x 18 x 18 in 20 inches in the ground over the charred point of stake and raised a mound 4 ft. in diameter and 3 ft. high for the corner to sections 31 + 32 on the township line between townships 3 + 4 north range. 23 E. N. W.

Returning to the south-west corner of sec. 31 T<sup>h</sup>. 4 N. R. 23 E. I set a rock 28 x 12 x 10 marked C. S. over a deposit of a bushel or more of small river washed rocks and raised a mound of earth five feet in diameter and 3 feet high for the corner to townships 3 + 4 north and 22 + 23 east.

Flora White makes affidavit that he placed the bushel or more of river washed rocks in the mound to this last above corner while the original post set by the Deputy U. S. surveyor was still standing and identified the top of the stake yet on the ground.

Folder 1083, Date 12-1910

Book: 1, Page: 4B & SA

The importance of the corners in this locality cannot well be overestimated on account of so many having been destroyed or never established on the ground.

Dec. 9 & 10 - 1910.

D. W. F. Reid

County Surveyor