

At the N.W. corner of section 33 T₄ S. R. 26 E. I find the original govt rock 20x7x5 properly notched lying on top of the ground, four furrows having been plowed N. S. E. & W. from the corner, from the testimony of Bamy Daugherty and James Daugherty present these furrows mark the original locus of the corner rock as set by the Deputy U.S. Surveyor. This testimony, the furrows and the further evidence by measurement hereinafter recorded confirms the original location of the corner at the intersection of the four furrows. To more permanently mark this corner I reset the rock 18 inches deep and made four deposits or references 10 links distant from the corner N. E. white earthenware 16 in below surface, N. W. broken clear glass 18 in. deep, S. W. Stone coal deposit 18 in deep, S. E. Iron pipe 12x1/2 in. 14 in. below surface for the corner to secs. 28, 29, 32 & 33 T₄ S. R. 26 E.

Thence I run North, 40 ch. find no corner, set temp stake. 80 ch. find no corner, set temp stake for corner to 20, 21, 28 & 29, 120, 02 ch. at a point 6 lks E. of 1/4 cor bet. Secs 20 & 21, which is a mound & rocks in a line of fence. Returning to N.W. cor sec. 28 Dug hole 2 ft. deep, deposited rock 8x6x4 marked with a (+) cross, partly filled hole deposited rock 14x8x6 marked C. S. and built mound of earth from four pits N. E. N. W. S. W. & S. E.

Returning to 1/4 cor. bet. Secs. 28 & 29, Dug hole 2 ft. deep. deposited old irons, partly filled hole and set the government rock found lying on top ground with 1/4 on it. Made for references deposit of stone

Folder 1085, Date 4-1911 6

Book: 1, Page: 5C+6A

coal 10 lks N. 2 ft. deep, and glass 10 lks E. 2 ft. deep. for the $\frac{1}{4}$ cor
between secs. 28+29 T₁S. R. 26 E.

April 13th 1911.

D. V. F. Reid
County Surveyor

Date 6-1911