

At S.W. corner sec. 36 T₁S. R. 25E. dug in county road, found point of charred stake, dug hole 2 ft deep set steel wagon axle stake and rock against it 18X17X12 in. marked C.S. for corner, made four references by deposits N.E., N.W., S.W. & S.E. 10 lks dist. from corner of stone coal charred from surface down 30 inches.

Thence I ran North; 40 ch. set temp. 1/4 stake, dug for remains of govt. stake but found no trace of it; 80 ch. set temp stake for N.W. cor sec. 36 T₁S. R. 25E.; dug for govt stake but found no trace of it; 120 ch. to rocky point found no trace of 1/4 cor on W. side Sec. 25 set temp 1/4 cor stake.; 160.08 ch. 10 lks E. of N.W. cor Sec. 25 a mound and rock in line of fence. Returned to N.W. cor Sec. 36 made corrections for corner, dug hole 2 feet deep, set steel wagon axle for cor. and made four references by deposits of charred stone coal 10 lks dist. from corner N.E., N.W., S.W., & S.E. from surface down 30 inches for the corner to sections 25, 26, 35 & 36 T₁S. R. 25E.

May 6th 1911.

D.W. F. Reid

County Surveyor.