

Folder 1089, Date 6-1911
Book: 1, Page: 7A

From the N. E. corner of Sec. 31 T_p. 25. R. 29 E. N. W. Iron North. At 40 ch. set
temp. 1/4 cor stake. At 80.08 ch. intersect E. & W. line 14 lks W. of corner to secs. 19,
20, 29 & 30. Returned to temp 1/4 cor and set it N. 4 lks + E. 7 lks. The government rock
marked 1/4 was lying on top ground near by. Dug hole 3 1/2 feet deep. deposited broken
glass and reset the government rock marked 1/4 for the quarter section corner
between secs. 29 & 30 T_p. 25. R. 29 E. Dug pits 5 ft. N. + 5 ft S. of corner. Made
deposits of glass 4 ft. E. + 4 ft. W. of corner for references.

Thursday June 1st 1911.

D. W. J. Reid
County Surveyor.