

At the corner to sections 14, 15, 22 & 23 Tp. 25. R. 26 E. W. 30. which corner is marked by a mound and four distinct pits. Dug in the mound, found point of government stake, drove crow bar in stake hole in mound, filled hole with fine stone coal, and drove a $\frac{3}{4}$ in. iron pipe 12 in. long. At 10 lks. S. deposited broken white earthenware from surface down 16 in., 10 lks. N. deposited broken clear glass same depth., 10 lks. E. deposited broken brown glass same depth, 10 lks. N. deposited 3 horse shoes 12 in. below surface. East 1.47 ch. lane fence. At 2 ch. E. drove $\frac{3}{4}$ in. galvanized iron pipe, 12 in long 10 in. below surface. At 2.39 ch. E. dug hole on W. line county road 24 in deep and deposited earthenware, crockery, glass and set rock 26x10x6 marked C.S. about 40 ft. N. of center of wagon track.

Nov. 13-1911.

D. W. J. Reid
County Surveyor