

Folder 1095, Date 4-1912

Book: 1, Page: 9C to 12A

From the quarter section corner between secs. 21 & 22 T<sub>1</sub>N. R. 27 E. T<sub>1</sub>M.  
I run North. At 40 ch. set temp. cor stk for secs 15, 16, 21 & 22 - 1 N 27 E  
Thence E. 40.46 ch. Dug & found government deposit of charcoal. Dug  
hole 32 in. deep against N. side deposit charcoal, leaving the deposit in  
place of original situs, Set post 2x4 - 4 ft. long marked C.S. deposited  
6 little rocks at foot, filled up hole set rock 13x10x7 in., on top char.  
deposit, marked C.S. and built mound 2 ft. high 3 ft diam. Made  
four references 10 lks. dist. from corner 4 1/2 in. below surface: N. E.  
rock 8x6x2 marked with O; N.W. rock 6x4x3 marked +; S.W. rock 18x8x4

marked with triangle  $\Delta$ ; S.E. rock  $7 \times 6 \times 5$  marked with letter  $\nabla$ . all to more permanently mark the quarter section corner between secs. 15+22  $\frac{1}{4}$  P., 1 A. R., 27 E. W. W.

Returned to temp sec. cor to secs. 15, 16, 21+22 and dug for deposit. Not finding it, ran North from temp cor and at 40.16 ch. was 18 lks. N. of  $\frac{1}{4}$  cor bet secs. 15+16 where dug & found charcoal deposit as per field notes. Dug hole on E. side charcoal deposit 1 ft deep to bed rock, set rock  $20 \times 12 \times 10$  marked C.S. against char. dep., built mound of earth  $2\frac{1}{2}$  diam & 18 in. high over it, the corner. Made four references 10 lks. dist. from cor. and 12 in. deep. N.E. rock  $10 \times 6 \times 3$  marked figure 4; N.W. rock  $10 \times 8 \times 6$  marked +; S.E. rock  $14 \times 6 \times 3$  marked triangle  $\Delta$ ; S.W. rock  $18 \times 8 \times 8$  in. marked letter A. All to more permanently mark the quarter section corner between secs. 15+16  $\frac{1}{4}$  P., 1 A. R., 27 E. W. W.

Returning to temp cor to secs. 15, 16, 21+22 making corrections, dug and found the original deposit of charcoal in the presence of Leroy Hill, Chas. Bartholomew, Al. Martin & Pat. Rork. This deposit is 40.21 ch. N. of the  $\frac{1}{4}$  cor. bet secs. 21+22 and 40.09 ch. S. of  $\frac{1}{4}$  cor bet secs. 15+16 and 2 lks. E. of straightline bet. them. Dug hole against S. side char. deposit leaving it in its original situ, set  $2 \times 4$ -3 ft long against S. side deposit; set rock in bottom of hole on S. side stake-rock  $14 \times 8 \times 3$  marked C.S. filled hole, set another rock  $16 \times 8 \times 8$  marked C.S. on top charcoal deposit, built mound 5 ft. diam & 3 ft. high and made four references 10 lks. dist. from corner & 18 in. deep. N.E. rock  $10 \times 6 \times 6$

situs, set 2x4-3ft long against S. side deposit, set rock in corner of hole.  
 Side stake-rock 14x8x3 marked C.S. filled hole, set another rock 16x8x8 marked  
 C.S. on top charcoal deposit, built mound 5ft. diam + 3ft. high and  
 made four references 10lks. dist. from corner + 18in. deep. N.E. rock 10x6x6  
 marked letter A; N.W. rock 6x5x3in. marked with a square  $\square$ ; S.W. rock;  
 S.E. rock 12x8x3 marked circle O, all to more permanently mark the  
 corner to sections 15, 16, 21 + 22 Twp. 1 N. R. 27 E. N.M. 1900ft above sea level  
 500 ft. above Butter Creek bottom. Tues. Apr. 9<sup>th</sup> - 1912.

From the quarter section corner between secs. 21 + 28 Twp. 1 N. R. 27 E. 3rd  
 West, at 40.03 ch. at a point 29lks S. of cor to secs. 20, 21, 28 + 29, a mound  
 and pits. Dug in mound and found charcoal deposit as per notes and  
 point of balm stake. The true course is S. 89°-36' E back to  $\frac{1}{4}$  cor on S. side  
 sec. 21 Twp. 1 N. R. 27 E. Set rock 18x12x5 in. on top charcoal deposit marked  
 C.S. and raised a mound of earth 2ft. high + 36 in. in diameter. Made  
 four references all 10lks dist. from corner and 1 ft. below surface  
 N.E. 9 small rocks; N.W. rock 6x4x2 marked F; S.W. rock 8x6x6 marked  
 C; S.E. rock 8x8x4 marked + all to more permanently mark the corner  
 to sections 20, 21, 28 + 29 Twp. 1 N. R. 27 E. N.M.

Thence I run North. At 40. ch. no sign of mound or pits. Dug all  
 around and found deposit of charcoal as per notes but at 39.91 ch from  
 the last above corner (S.W. cor sec. 21) and on due north line. Dug hole on N.  
 side of and against charcoal deposit - leaving deposit in its original  
 situs set a post 4ft long marked C.S. and set a rock 18x12x6 on top of  
 charcoal deposits, built mound of earth 2ft. high + 3ft in diameter

and made four references all 10 lks. dist. from corner and 1 ft. below surface. N. E. rock 12x6x2 marked M; N. W. rock 10x6x4 marked V; S. W. rock 6x4x2 marked +; S. E. rock 14x6x6 marked N all to more permanently mark the quarter section corner between sections 20 & 21 Twp. 1 N. R. 27 E. W. M.

Thence Down North, At 20.60, from last above corner, cross trail to Willow Creek. At 40. ch. dug and at 40.09, from last above corner, found charcoal deposit as per notes but 10 lks. E. of due north line. Dug hole 34 in deep on N. side of charcoal deposit and against it. Set cast iron oven stove door against char. dep. and deposited more charcoal in bottom of hole, set rock 14x8x6 marked C, S. 8 in below surface, set a charred post on top char. dep. raised mound of earth 2 ft high 3 ft. diam, made four references, N. E. cast iron stove door 4 1/2 x 4 1/2 in.; N. W. stove lid 2 ft. below surface S. W. Stove door - cast iron 14x6 in. 3 draft holes in it; S. E. stove lid all 10 lks distant from corner and 1 ft. or more below surface. South 45 lks dug hole 28 in. deep, set cast iron piece of stove door and little round rock, filled hole to 14 in. deep, set other piece stove door and set rock 6x6x4 marked N. C. for witness to corner on S. side county road running E. & W. This section corner is in county road about 12 lks. from wagon track and whenever the industrious road supervisor happens along he will, according to prevailing custom among them destroy every evidence of the corner that is in sight. Therefore all the above, rocks, irons, charcoal &c. the more permanently to mark the corner to sections 16, 17, 20 & 21 Twp. 1 N. R. 27 E. W. M. There is not, perhaps, any other corner from this one north to the Twp. line to be found as the the line and what charcoal has not been dug up

them destroy every evidence of the corner that is in sight. Therefore all the above, rocks, irons, charcoal &c. the more permanently to mark the corner to sections 16, 17, 20 & 21 T<sub>1</sub>P. 1 N. R. 27 E. W.M. There is not, perhaps, another corner from this one north to the T<sub>1</sub>P. line to be found as the county road follows the line and what charcoal has not been dug up and destroyed by carelessness and ignorance has been tramped out by teams.

Thence Iron S. 89°-57' E. on N. line Sec. 21 - T<sub>1</sub>P. 1 N. R. 27 E. citing to flag set on N. E. cor said Sec. 21. At 40 ch. dug over much ground and finally found charcoal deposit as per notes which charcoal deposit is 40.08 ch. N. of N. E. cor Sec. 21 and 4 lks N. of straight line from sec. cor to Sec. cor. Dug hole 3 ft. deep, set tamarack post 5 in by 4 ft. marked C. S. Against E. side charcoal deposit leaving the deposit intact and in its original situs, set steel thimble skew of wagon axle at foot of post 36 in deep, set rock 14x10x8 in. marked C. S. on top charcoal deposit and built mound of earth 3 ft high 36 in. diam. Made four references 10 lks dist. from corner and 16 in. deep. N. W. rock 12x4x3 in. marked H; S. W. rock 8x6x3 marked Y; S. E. rock 8x6x3 in. marked +; N. E. rock 12x12x5 in. marked Z - All to more permanently mark the quarter section corner between sections 16 & 21 T<sub>1</sub>P. 1 N. R. 27 E. W.M.

Thence Iron South to establish the center corner said sec 21. setting temporary stakes every 20 ch. Intersect S. boundary 9 lks N. of 1/4 corner. The course of this center line is therefore S. 0°-04' E. From the 1/4 cor on N. side said Sec 21 Iron E. to flag on 1/4 cor on E. side sec. 21

Folder 1095, Date 4-1912

Book: 1, Page: 9C to 12A

setting flag on corrected N. & S. center line. Dug hole 2 ft. deep, set rock 18X8X10 marked C.S. for center corner said sec. 21. Set old wagon bolster stake by rock on the N. side. Made four references. N. E. rock 10X6X4 in. marked +; N. W. rock 12X8X2 in. marked N; S. W. rock 12X12X8 marked O; S. E. rock 14X10X6 marked H all 10 lks distant from corner and 12 inches below surface raised mound over corner 2 1/2 ft high and 4 ft. in diameter. Dug four pits N. E. S. & W. 18 in. diam. 2 1/2 ft. deep. All to permanently mark the center corner to section 21 T<sub>4</sub> N. R. 27 E.

April 9<sup>th</sup> to 11<sup>th</sup> - 1912.

D. W. J. Reid  
County Surveyor.