

At the corner to sections 27, 28, 33 & 34 T₁N. R 27 E. N. W. In company with Lou Watterberger and E. P. Jarrow who thought they knew the location of this corner we dug and found the charcoal of the charcoal deposit as per field notes and two pieces of sickle bar of mower drove into the ground at the charcoal. Dug hole 2 ft. deep, deposited rock 6x6x5 in, marked with a cross + in bottom of hole, filled it up to 1 ft deep put the charcoal from the deposit into hole, set a rock 12x10x10 marked C.S. on top charcoal and against sickle bar and built mound of earth upon the corner 2½ ft. high and 4 ft. diameter. Made four references, N.E. rock 8x6x5 marked H; N.W. rock 12x6x4 marked Δ; S.W. rock 10x8x5 marked A; S.E. rock 8x6x5 marked □ all 10 ft distant from corner and 2 ft deep. Deposited over each reference broken glass 12 inches below surface. All to more permanently mark the corner to sections 27, 28, 33 & 34 T₁N. R, 27 E. N. W.

April 16-1912.

D. V. S. Reid
County Surveyor.