

From the N.W. corner of Twp. 2 N. R. 23 E. N.W. 3 run south. At 40 ch. find the government rock 12x8x4 in. lying on the ground, having been removed from its original setting. At 80.12 ch intersect E+W. line 9 lks N of corner, which is a frost in a mound of light sandy soil. Returned to the temporary $\frac{1}{4}$ stk. + set it south 6 lks. and east $4\frac{1}{2}$ lks. Dug hole 18 in. deep, set the government rock marked K therein, set rock 16x10x5 in. marked C.S. against N. side of it + built mound 18 in high + 2 ft. diam. Made four references 15 lks. dist from corner and 12 in. below surface, N.E. rock 8x5x4 marked H; S.E. rock 19x11x4 in marked +; S.W. rock 6x6x5 marked Δ ; N.W. glass bottle, all to more permanently mark the quarter section corner on the Twp. line on the west side of section 6 Twp. 2 North Range 23 E. N.W.

April 25th 1912.

D. W. F. Reid
County Surveyor.