

Folder 1098, Date 4-1912

Book: 1, Page: 13A

From the corner to sections 20, 21, 28 & 29 Twp. 2 N., 23 E., N. W. Iron South,
at 40 ch. set temp. $\frac{1}{4}$ cor stk. 80.00 ch. set temp. Sec. cor to secs. 28, 29, 32 & 33,
120.00 set temp $\frac{1}{4}$ stk 160.32 ch. intersect township line 11 lks E. of corner.

Returned to temp. cor to secs. 28, 29, 32 & 33 and set it south 16 lks & W. $5\frac{1}{2}$ lks, dug
hole set rock 12x8x6 - 4 in. below surface marked C.S. Made four references 10 lks
dist from corner N. E. iron rod; N. W. cast iron piece machinery; S. W. glass & S. E.
iron rod $\frac{1}{2}$ round 16 in long. Set rock 22x14x6 in marked L.R. (line rock) on S line
sec 28 - 2 N., 23 E. at intersection of fence on S. W. Side County Road - 2 ft deep
with R. R. fish plate against it and set rock 20x12x4 marked L.R. (line rock)
on E. line sec. 29 at intersection of fence on S. side Co. road 2 ft. deep under fence
with iron rod against S side of it. All to more permanently mark the loca-
tion of the corner to sections 28, 29, 33 & 32 Twp. 2 N., R. 23 E., N. W.

Apr. 26" 1912

D. W. F. Reid
County Surveyor.