

At the quarter section corner between sections 24 & 3 T₄P. 5 S. R. 27 E. NW. found the government rock standing as originally set by U.S. deputy surveyor and three witness trees as per field notes but the courses and distances will not locate the corner in the place it now stands or in any one place, I therefore mark the location of the rock more permanently as follows; Set the rock marked 1/4 down to surface with iron rod against it, four references 10 lks distant and 12 in. below surface S.E. cast-iron cog wheel 8 in. diam.; S.W. deposit of broken earthenware; N.W. Broken glass, horse shoe & iron spindle; N.E. broken glass. From the corner a pine tree 20 in. diam S. 65° E. 44 lks. marked 1/4 S. B.T. A pine 26 in. diam. N. 40° W. 55 1/2 lks marked 1/4 S B.T.

From the 1/4 corner between secs 24 & 3 T₄P. 5 S. R. 27 E. Iron North. 20.00 ch. Yellow pine 20 in diam. blazed for line tree 72 ch. road 73.30 creek 77.75 corner. Found rock on top ground by hole from which it had been recently removed. Rock being 15x12x6 in. marked 4 notches on one side & 2 on another side. Reset the rock. Dug hole 2 1/2 feet deep set rock in bottom 14x12x10 marked C.S. and set original rock 15x12x6 in. on top & raised mound 18 in high & 3 ft. diam, with four holes N. E. S. & W. Made four references 10 lks. dist, from corner & 12 in. below surface N.W. rock 12x10x5 marked A; S.W. rock 6x5x3 marked +; S. E. rock 8x7x3 marked H; N. E. rock marked
The true bearing and distance to each witness tree as follows;
Yellow Pine 30 in. diam. N. 21°-54' E. 169 lks. marked T. 4 S. R. 27 E. B.T.; Yellow Pine 24 in. diam. S. 71°-00' E. 265 lks marked T. 5 S. R. 27 E. S. 2 B.T.; Quakensap 10 in. di. S. 19°-00' W. 245 lks. T. 5 S. 27 E. S. 3 B.T.

April 28" 1912.

D. V. J. Reid,
County Surveyor.