

Folder 1100, Date 5-1912

Book: 1, Page: 14A

46
 From the N. E. corner of sections 3 T₁P. 55, R. 27 E. N. W. Iron North. 40 ch. set temp. $\frac{1}{4}$ corner, 80.19 intersect E + W. line 23 lks E. of corner, a rock 7x5x5 having 2 notches on one side - no trees marked for witness trees, Set post $3\frac{1}{2}$ ft. - 1 ft. in ground at corner marked C. S. from which Yellow Pine 32 in. diam. bears N. 8° -48' E. 121 lks, marked B. T. C. S.; A Bull Pine 22 in diam. N. 40° -W. 103 lks marked B. T. C. S. All to more permanently mark the corner to sections 26, 27, 34 + 35 T₁P. 45, R. 27 E. N. W. The first line or two above should read From the N. E. corner of Sec. 3 T₁P. 55, R. 27 E. Iron N. 31° -10' W. 6.96 ch. to sec. line between secs. 34 + 35 T₁P. 45, 27 E. at a point 5.95 ch. N. of S. E. cor Sec. 34. then with 5.95 ch. from cor Iron on North and at 40 ch. from the S. E. cor sec. 34 set temp. $\frac{1}{4}$ stk. Returned to the temp $\frac{1}{4}$ cor bet. secs 34 + 35 and set it over N. $9\frac{1}{2}$ lks and N. $11\frac{1}{2}$ lks. Dug hole set rock 18x10x9 for corner from which a round top bed rock 20x20 bears S. 62° -45' W. 11 lks marked B. R. and corner rock marked C. S. to more permanently mark the quarter section corner between sections 34 + 35 T₁P. 45, R. 27 E. N. W.

May 6th 1912.D. W. F. Reid
County Surveyor.