

From the N.W. corner section 30 on the T_p. line, Iron East-40 ch. set temp $\frac{1}{4}$ stk. 82.86 ch. intersect N. & S. line 58 lks. N. of corner. Return to temp stk bet secs. 19 & 30 T_p, 3 S. R 27 E. N.W. Dug hole 12 in. deep to bed rock. Set rock 34X24X20 in. marked C. S. at a point 29 lks S. and 148 lks E. of temp. stk. for $\frac{1}{4}$ corner and set the government rock marked $\frac{1}{4}$ which was lying on ground near by, having been removed from its original location. Built mound of earth and rocks. Made four witnesses N.E. rock 14X10X5 marked +, N.W. rock 10X7X5 marked I, S.W. rock 14X10X8 marked H and S.E. rock 14X8X4 marked D all four 10 lks dist. from corner and buried 6 in. below surface - all to more permanently mark the location of the quarter section corner between sections 19 & 30 T_p, 3 S. R 27 E, N.W. May 23-1912 - D.V. Reid - Co. Surveyor.