

At the quarter section corner between sections 3 & 4 T₄ S. R. 29 E. found the government rock, marked 1/4, tipped over and nearly out of the ground.

Reset this rock and set a rock 14x8x4 marked C.S. against the E. side of it and made a mound of rocks over the corner.

Made four references 10 lks. dist. from the corner, N.E. deposit of broken glass; N.W. hay rake spoke-steel 10 in long; S.W. broken earthenware and iron rod 3/8x10 in.; S.E. steel hay rake spoke - all the references from surface down to bedrock about 12 inches. All to more permanently mark the identical spot of the original location of the quarter section corner between sections 3 & 4 T₄ S. R. 29 E. The section corner S. of this is gone or rather the rock set to mark the corner has been removed and the "identical spot" forever lost.