

At the corner to sections 4, 5, 8 & 9 T₁. 35. R. 29 E. found the corner rock out of the ground but the hole plain to be seen and two years ago saw from this corner S. and at 40 ch. found the original corner stake. The identity of this spot (the cor to sec. 4, 5, 8 & 9 - 35 - 29 E.) is beyond question I therefore dug hole deeper & reset the government rock. 22x18x3 - 4 notches on one edge and 2 notches on another edge. Set another rock against it 14x10x2 marked C.S. piled rocks around corner and made four references, 10 lbs. dist. from corner and from one to two feet deep. N.E. two steel spokes from hay rake wheel 24 in. long 30 in. down & 6 in. below surface; N.W. Iron $\frac{1}{4}$ x $\frac{1}{4}$ x $\frac{1}{4}$ in. 8 in. below surface; S.W. Piece steel spring $\frac{1}{4}$ x $\frac{1}{8}$ x16 in. 6 in. below surface; S.E. deposit of glass and piece strap iron 6 in. long. All to more permanently mark the identical spot of the location of the original corner to sections 4, 5, 8 & 9 - 35. 29 E.