

At the quarter section corner between secs 8+9 T₄S. R. 29 E. to which I ran as stated in last paragraph above. Found the original quarter stake. Dug hole 8 in deep to bed rock, set rock 16X10X5 marked $\frac{1}{4}$ C.S. and made mound of rocks. Made four references N.E. iron $\frac{1}{8}$ X $\frac{1}{4}$ X12 in. and several smaller pieces iron and sickle-bar guard as deep as could drive crow-bar; N.W. iron $\frac{1}{4}$ X $\frac{3}{4}$ X12 in. and several smaller pieces iron; S.W. iron $\frac{1}{4}$ X1X12 in.; S.E. steel spoke from hayrake wheel and forked iron 12 in. long, all 10 lks. dist. from corner and all to more permanently mark the $\frac{1}{4}$ corner bet. secs. 8+9-35-29 E.