

Folder 1106, Date 6-1912

Book: 7, Page: 16D-17A

At the corner to sections 16, 17, 20 & 21 Sp. 35, R. 29 E. N. M. found the government rock fallen over with few rocks to mark the stone mound but sufficient to determine the original situs of the corner rock. Lowered the rock to bed-rock about 12 inches. The rock 20x10x10 having 3 notches on one edge and 3 on another. Set another rock 12x7x5 marked C.S. against it and rebuilt the stone mound. Made four references 10 lbs dist. from corner and down as deep as could drive crow-bar. N.E. broken brown

glass bottle and cog wheel $4 \times 2\frac{1}{2}$ diam; N.W. iron $\frac{1}{4} \times 1 \times 12$ in. & round iron $1\frac{1}{2} \times 6$ in.; S.W. broken clear glass bottle & piece steel wagon axle thimble 10 in long on top broken glass 24 in deep; S.E. piece of cast iron wagon thimble 5 in. long 8 in. deep; Deposited in the corner pieces of iron as deep as 16 in. All to more permanently mark the the identical spot of the location or situs of the corner to sections 16, 17, 20 & 21 - T₄. 3 S. R. 29 E. N.W.

June 21st 1912.

D. V. J. Reid
County Surveyor.