

At the quarter section corner between sections 27 & 34 T<sub>4</sub>P. 2 S. R. 26 E. N. W.

Dug hole 3 ft. deep. Set 2x4-4 ft. long, deposited stone coal at bottom & also piece of bolster pin and 6 inch. stub of axle, filled hole partly, set pipe 3 in x 2 ft., raised mound of earth 2½ ft. high & 4 ft. diam. Made four references; S. E. deposit of fine stone coal from surface down 36 in. at a distance of 10 lks. from corner.

S. W. Deposit of broken glass from surface down 3 ft. at 10 lks distant from corner.

N. W. Deposited cast iron stove grate from 1 ft. to 2 ft below surface and set steel axle stub 8 in long on top of grate at a distance of 15 lks from corner.

N. E. Deposit of broken earthenware and whole glass bottle 12 in. below surface at a distance of 13 lks from the corner. This corner is in an old fence now the bottom of the posts still to be found which fence was built over the corner while the corner stake was still standing as per the evidence of W. C. Minor. The present E & W. fence is 4 ft N. of corner.

July 6<sup>th</sup> 1912.