

From the corner to sections 14, 15, 22 & 23-25, 26 E. Iron west 40 chains,
Dug, found old stake. Dug hole 2 ft. deep, set rock 5X4X1 marked + in both
low hole & set rock on it 12X4X4 marked C.S. partially filled hole & set rock
14X12X1/2 marked C.S. for corner raised mound 2 1/2 ft high 3 ft. diam.

Made four references as follows; N.E. rock 8X5X5 marked M; N.W.
rock 10X4X4 marked C; S.W. rock 6X6X2 marked H; S.E. rock 6X6X1/2
marked S. All 10 lks. dist. from corner and 12 inches below surface.
and to more permanently mark the quarter section corner between
sections 15 & 22 Twp. 25. R. 26 E. W.M.

July 9th 1912.

D. V. Reid
County Surveyor