

Folder 1109, Date 8-1912

Book: 1, Page: 17D+18A

At the corner to sections 35 + 36 on the Base Line Twp. N. R. 26 E.
Dug and found the charcoal deposit described in field notes of the
government survey. Dug hole 16 in. deep deposited broken brown glass bottle
against N. side charcoal deposit which is left undisturbed. Deposited
on the glass a rock 6x6x4 marked +, Set a rock on top against N. side charcoal
14x12x6 marked C.S. for corner. Raised mound 2 ft high 3 ft diam.

Folder 1109, Date 8-1912

Book: 1, Page: 170-18A

Made four references as follows; N.E. broken white earthenware 12 in deep; N.W. rock 6X6X4 marked T 10 in deep; S.W. piece cast iron stove 16X5 18 in deep. and something S.E. all 10 lks dist and to more plainly and permanently mark the corner on the Base Line to secs. 35 + 36 in T₁ N. R. 26 E. W. M.