

At the S. E. corner T₁ N. R. 26 E. N. M. on the Base Line. Dug and found the bottom of the post described in field notes, in a back furrow ridge running N + S. Dug hole 2 ft. deep to bed rock. Deposited rock 14X10X10 marked + partly filled hole, set rock 15X11X9 marked C.S. on top for corner, raised mound 2½ ft. high 4 ft. diam., dug pits N. E. + W.

Made four references 10 kts. distant from corner as follows: N. E. rock 8X7X9 marked A, N. W. rock marked Y + cast iron piece of stove, S. W. rock marked K, S. E. rock marked H and cast iron piece stove, all 12 inches below surface, all to more plainly and permanently to mark the corner on the Base Line to secs. 36 T₁ N. R. 26 E. and sec. 31 T₁ N. R. 27 E. N. M. Aug. 3rd 1912