

At the S.E. cor Sec. 22 T<sub>1</sub>N. R. 26 E. W. W. Dug and found the charcoal deposit as per field notes. Dug hole  $2\frac{1}{2}$  ft. deep, deposited rock 12X10X5 marked +, partially filled hole, set rock 11X10X4 marked C. S. for corner, also deposited in hole rock marked A 12X8X5 top rock at surface - being in center of road put them down deep. Set rock 6X6X5 marked W. C. 33 ft to West under wire fence running west, fence also running north, for witness to corner. Made four deposits as follows; N. E. stone coal deposit from surface down 30 inches and rock on top 5X4X4 in. marked H; N. W. broken glass from 12 to 24 in. below surface and rock, unmarked, 6X5X3 on top 9 in. below surface; S. W. rock 13X12X8 marked K 12 to 25 in below surface; S. E. Deposit of fine stone coal from surface down 34 inches and all four references 10 lks dist. from corner. All to more permanently mark the corner to sections 22, 23, 26 & 27 T<sub>1</sub>N. R. 26 E. W. W.

Aug. 5<sup>th</sup> 1912