

At the quarter section corner between sections 22 & 23 T₁N., R., 26 E.,
Dug, found charcoal as per field notes. Dug hole 2 ft. deep, laid in bottom
rock with + on it, throw in 4 other rocks, Set rock 24x10x8 marked C.S. for $\frac{1}{4}$ cor.

Made four references 10 lks dist. from corner as follows; N.E. clean broken
glass bottle from surface down 30 inches; N.W. Deposit of fine stone coal
from surface down 40 inches; S.W. 2 pieces cast iron ft. long each from
10 in to 30 in below surface; S.E. rock 16x8x10 marked H 10 in. below surface
to 26 below surface. All to more plainly and permanently mark the $\frac{1}{4}$
corner between sections 22 & 23 T₁N., R., 26 E., N. W. end being the S.E.
corner of Deardorfs homestead in Sand Hollow.
Aug 5th 1912