

Folder 1113, Date 8-1912

Book: 1, Page: 17A

At the corner to sections 1, 2, 11 & 12 Twp. 15, R. 26 E., N. 20 W. Found the rock used as fence anchor, but on the testimony of David Legend and Wm Legend that the corner post of the fences running E. & W. was set by the rock years ago while the rock stood as originally set accepted the post for the corner. Dug hole on N. side post marked the rock W. S. & C. S., it having the proper notches on it, viz 5 notches on one edge and one notch on another edge, and set it to mark the corner. Made four references as follows: N. E. rock 10x4x3 in. marked A 10 in. below surface; N. W. Deposit of stone coal from 24 to 30 in below surface and whole dark glass bottle top down 12 in below surface; S. W. Piece cast iron 12 in long from 12 to 24 in below surface & rock 4x4x3; S. E. Deposited fine stone coal from surface down 30 in. All 15-16<sup>1</sup>/<sub>2</sub> dist. from corner.