

At the quarter section corner between secs. 1 and 2 T₁P. 15, R 26 E, N. 11, W. 1,
Found rock standing by corner post to fences running S. & N. rock wrong
end up, marked 1/4 but on the testimony of the Heynd Bros. above that the
posts for this corner have stood in this identical spot by the rock
when and where it originally stood accept this as the true corner.
Dug hole 30 in deep deposited pieces cast iron, Set the 1/4 rock then on
against the N. side corner post of fences, Set rock 30x11x4 marked C.S.
on E. side fence post and against the 1/4 rock. Made four references
N. E. Deposit stone coal 14 to 24 in. below surface + small rock 10 lks
dist from corner; N. W. Deposit stone coal from surface down 30 in. at
a distance of 20 lks from corner; S. W. broken clear glass bottle 12 in
below surface 7 lks distant from corner; S. E. 2 pieces cast iron
tin can and fine stone coal 10 lks distant from corner.

Aug. 5th - 1912

D. V. F. Reid

County Surveyor.