

Folder 1115, Date 3-1910

Book: 1, Page: 19C

8-1912

9A-20A

Commencing at the N.E. corner sec. 25 Tp. 3 N, R. 23 E, N.W. running  
thence on township line south. 40 ch.  $\frac{1}{4}$  stake lying on ground. 80 ch.  
Set temp stk for S.E. Cor Sec. 25. 120.56 ch. the  $\frac{1}{4}$  corner rock firmly  
Set in ground marked  $\frac{1}{4}$  is 47 lks to East. Returned to S.E. Cor Sec.  
25 set temporary stk over  $35\frac{2}{3}$  lks. East and 36 lks south. Set post  
scribed C.S. for corner. Set rock 14X10X8 marked C.S. alongside and  
made four deposits 10 lks dist from corner. S.W. broken glass  
bottle, N.W. stone coal and charcoal, N.E. + S.E. stone coal and  
charcoal.

Mar 30-1910.

D.V.F. Reid - Co. Surveyor