

charcoal,

Mar 30-1910.

D. V. F. Reid - Co. Surveyor

At the quarter section corner between sections 22 & 27 - T₄N.,
R. 25, R. 26 E., W. 1/2. I have known the location of this corner for the
past eleven years and have seen the rock marked to designate

Folder 116, Date 8-1912

Book: 1, Page: 190-20A

the corner and its locus. The rock was carried away to build a crib of rocks to anchor a fence probably. I noted the spot where the rock stood after it was taken away having built up the rock mound around it and added rocks to the mound on several occasions. After the rock having the 1/4 on it was removed many of the smaller rocks of the mound remained in a circular form and later they were scattered but the bare spot, having no grass upon it, where the corner rock stood remained plain to be seen to the present time. Recently I measured from the N.E. Cor sec. 27 same T.P. West to this spot and the 40. chains came to it exactly, therefore I mark and perpetuate the identical spot where the rock marked 1/4 stood for so many years as the government corner, as follows: - Dug hole 6 inches deep, as deep as hole could be dug, to bed rock, set rock 14x5x2 in. marked C.S. for corner, in the hole where the government rock having 1/4 on it stood. Made four references. N.E. 15 lks drove crowbar 6 in to rock, deposited therein finely broken clear glass; N.W. Deposited fine stone coal from surface down 6 in to rock, punched the coal down with crowbar among the rocks. S.W. 15 links deposited piece of cast iron. S.E. 15 lks, drove crowbar down to rock 6 in. deposited broken earthenware from surface down 6 in.

Aug. 26th 1912.

D. V. J. Reid Geo. Surveyor.