

At the $\frac{1}{4}$ corner on the N. side sec. 26 T₄S, R₂₅W, T₄S, R₂₅W, M. The pits and mound are yet descimable. Dug hole 2 ft. deep, deposited fine stone coal, Set post 4 in square marked C.S. $\frac{1}{4}$ on E. S. 23 on N. & S. 26 on S, raised mound 1 ft. high. References; - N. E. dug hole, 10 lks dist. from corner, 14 in. deep, deposited cast iron stove grate 12 in. long, N. W. Drove crowbar 10 lks dist. 20 in. deep filled hole with broken clear glass from surface down 20 inches deep. S. E. 10 links, drove $\frac{3}{4}$ in galvanized iron pipe 16 in long from 6 to 22 in. down below surface, S. W. 10 lks, Drove crowbar 24 in. deep filled hole with fine stone coal from surface down.

Aug 26" 1912.

D. V. F. Reid Co. Surveyor.