

Folder 1119, Date 8-1912

Book: 1, Page: 21A

From the last above corner Iron East. 40 ch. the corner to Secs 23, 24, 25  
+ 26 - Twp. 2 S. R. 26 E. Pit and mound dunce to be seen. Fence running  
through the corner N. + S. and fence running East. Dug hole 28 in deep, de-  
posited pint and half fine stone coal, set post, red fir, 4x4x26 in, marked  
C.S. and S. 26 S 25 - S. 24 S. 23. Made four references: N. E. <sup>10 lks</sup> round inch  
iron 8 in. long from 10 to 18 in below surface: N. W. <sup>10 lks</sup> irregular ornamental  
fence iron 16 in long from 5 to 21 in below surface: S. W. 10 lks rock 12x10x8  
marked + 8 to 24 in below surface. S. E. Deposit fine clear glass 2 5/8 in  
below surface and 10 lks distant from corner.

Aug. 26-1912

D. V. F. Reid Co. Surveyor.