

At the $\frac{1}{4}$ corner between secs. 34 & 35 T₄P. 25, R. 26 E., N. W. Established by survey from sec corner N. to sec corner S. The original $\frac{1}{4}$ rock gone.

Set a rock marked C.S., 3 ft north of shallow gulch, made mound of rocks. Made four references. N.E. 15 lks deposit: fine clear glass 10 in deep and piece of iron 4x2x $\frac{3}{8}$, N.W. 15 lks. Iron pipe $\frac{3}{4}$ x7 and deposit of fine stone coal from surface down 10 in deep. S.W. 39 lks. round $\frac{1}{2}$ in x 18 in. iron rod and fine stone coal from surface down 20 in. S.E. 25 lks. deposit of broken earthenware from surface down 16 in to bed rock, 6 ft. S. of shallow gulch. The S.W. deposit is on line with fence running N. 30 or 40 ft. distant. Bed rock near surface + slope to E. + S.E.

Aug 26 - 1912

D. D. F. Reid Co. Surveyor.