

Folder 1123, Date 8-1912

Book: 1, Page: 22A

At the $\frac{1}{4}$ corner on S. side Sec. 34 T_{p.} 25, R. 26 E. Several years ago surveyed N. from S. E. cor. Sec. 34 and at 40 ch. found mound and pits and dug, found point-chained stake & char and drove iron rod $\frac{3}{8}$ round $\times 36$ in top 10 in. above surface. Today rod is in place but mound and pits gone, therefore desirable to mark more permanently the identical spot where the original stake stood.

Dug hole on S. side rod against it 36 in. deep, deposited fine stone coal, partly filled hole, deposited broken crockery-ware, set rock 2.3 \times 10 \times 5 in. marked C. S. against the said iron rod on the S. made earth mound 18 in high, 36 in diam. made four references: N. E. deposited a brick 12 to 20 in below surface 12 lks. dist from corner. N. W. 12 lks. deposited an old flat-iron 12 in below surface in flowed ground. S. W. 12 lks fine stone coal and $\frac{1}{4}$ in. galv. iron pipe 8 in long from 6 in to 24 in below surface. S. E. 12 lks. Deposit of broken clear glass from surf. down 30 in. in pasture land.

Aug. 26-1912.

D. V. J. Reid Co. Surveyor.