

At the S.E. corner sec. 34 2S. R. 26 E. W. M. Dug and found the point of the government stake, drove iron rod $5/16 \times 12$ in in it. Dug hole 3 ft. deep, deposited fine stone coal, chopped it down with spade, partly filled hole, deposited several small pieces cast iron stove grate, Set rock $14 \times 8 \times 7$ in. marked C.S. against south side iron rod, and top rock at surface. Made four references: N.E. 5 lks deposit of broken blue & brown glass from surface down 30 inches. N.W. 5 lks. deposit of broken earthenware from surf. down 30 in. S.W. 2 1/2 lks. Dug hole 28 in deep deposited several pieces iron & set a cast iron stove grate 10 to 28 in below surface. S.E. 8 lks. Deposited fine stone coal from surf. down 30 inches.

Aug. 27-1912.

D. W. F. Reid Co. Surveyor.