

At the S. E. corner sec. 35 T<sup>4</sup> S. R. 26 E. N. W. marked by a rock which, being in the county road is liable at any time to be plowed up or otherwise changed from its proper location as is being done right along, therefore deem it proper to perpetuate its true locus.

Drove iron pipe  $1\frac{1}{2}$  in diam. on south of rock against it. Made four references as follows; N. E. 6 lks. drove crow bar 30 in. deep filled hole up to surface with fine stone coal. N. W. 6 lks. Drove crow. 30 in. deep filled hole with broken earthenware. S. W. 6 lks. Drove Crow. 30 in. deep, filled hole with broken crockery. S. E. 6 lks. Drove Crow. 32 in., filled hole with broken clear glass up to surface.

Aug. 28-1912

D. V. F. Reid - Co. Surveyor.