

At the corner to secs. 21, 22, 27 & 28 T₁ S. R. 27 E. N. W. This corner is located at the mouth of a canyon coming down from the north and also just south of a gulch 4 to 5 feet deep which gulch was ripped out during this summer and the water ran over this corner rock. In such location it is liable to be swept away at any time. The $\frac{1}{4}$ cor. south of it and the sec. cor. 1 mi S. of it are gone and no trace of them remains and the quarter corner $\frac{1}{2}$ mi S. stands in the bank (lowdown) of willow creek. Therefore the importance of preserving this corner. Rock standing firmly set in ground in mound of rocks, three notches on E and 2 on south, Drove crow bar on N. side 30 in deep, filled hole with fine stone coal, drove crow bar 20 in. deep on S. side rock and drove $\frac{3}{4}$ in iron pipe 18 in long 2 in below surface.

Made four references as follows; - N.E. 10 lks. Drove crow. 30 in. filled hole with broken clear glass up to surface. N.W. 10 lks. drove crow. 30 in. deep, filled hole with fine stone coal to surface. S.W. 10 lks. drove crow. 30 in. filled hole with charred stone coal. S.E. 10 lks. drove crow 13 in. deep and filled hole with broken crockery. Built mound of rocks.

Aug. 28-1912

D. V. J. Reid Co. Surveyor.