

crow 13 in. deep and filled with broken crockery. Built mound of rocks.

Aug. 28-1912

D. V. F. Reid Co. Surveyors.

At the  $\frac{1}{4}$  corner on S. side sec. 21 - T<sub>4</sub>P. 25. R. 27 E. N. W.  
Ran from the sec cor on the east to the sec. cor on the west

Folder 1128, Date 8-1912

Book: 1, Page: 23D-24A

Setting temp. quarter stake and found the temp stake to be at the true location of the quarter corner in a fence running E & W. and one running N. In setting the fence posts the corner marker, a stake, was destroyed.

Dug hole 20 in. deep punched hole in bottom 6 in. deep deposited in latter hole broken clear glass, Set rock 22x4x6 in marked C. S.

1/4 for corner. Made four references as follows; — N. E. <sup>10 lks</sup> drove crowbar 24 in deep in hardpan filled hole with fine stone coal 6 to 24 in.

N. W. 10 lks. drove crow. 18 in. in hardpan filled hole with broken brown glass to surface. S. W. 10 lks. Drove crow. 18 in. filled hole with charred stone coal to surface. S. E. 10 lks. drove crow. 30 in deep filled hole to surf. with broken earthenware to permanently mark the quarter sec. corner on the south side said sec. 21.

Aug. 28-1912

D. V. J. Reid - Co. Surveyor.