


Quarter corner between Secs. 4-5 T_{p.} 2 S. R 37 E. W. M.

From the corner of sections 4-5 on township line between T_{p.} 1 and 2 South, I ran line South $0^{\circ} 15'$ East, as per field notes 40.12 chains and set stake for temporary $\frac{1}{4}$ corner, thence on $S 0^{\circ} 15' E$ 40.00 chains, as per field notes, and the line passed directly through a pile of rocks in fence corner where a stone was found which tallied with the field notes as the original stone placed for the corner to sections 4-5-8 and 9, but the measurement of 40.00 chains passed beyond the corner 49 links. I then measured South 40.00 chains from stone found at the fence corner and found a stone marked $\frac{1}{4}$ laying on top of the ground about 6 ft. East of a slight raise or mound which looked very much like the old corner. I dug in mound and found rotten end of a fence post which indicated that the place was the original $\frac{1}{4}$ corner between sections 8-9. Returning to the line between sections 4 and 5 I found that the distance, which I found by two careful measurements, was 37 links less than 1 mile when the field notes give the distance as 1 mile 12 links. I returned to temp stake at $\frac{1}{4}$ corner between secs. 4-5 and established a corner 12 links North of the measurement of 40.12 chains from the section corner of 4-5 on T_{p.} line. To mark the corner I dug a hole 30 inches deep and poured in about $\frac{1}{2}$ gallon of fine coal (screenings). Set stone of ~~solid~~ triangular shape  26 x 14 x 5 with apex up marked $\frac{1}{4}$ CS on East side for corner. Drove two holes 2 inches square and 30 inches deep 10 links NE and SW respectively from stone, and filled to surface with fine coal (screenings) as witness corners.

Mar. 3 1914

Joy M. Turner Co. Surveyor