

Folder 1133, Date 4-1914

Book: 1, Page: 27B

Folder 113

Book: 1

Commencing at the $\frac{1}{4}$ corner between Secs. 1 and 6 Tp. 5 S Rs. 25 and 26 E.W.M.

Thence South 6' East as per field notes 41.15 chains found stone 14x14x5 marked 5/26 on West face in mound of stone for corner to Secs. 6-7-1-12, thence S 89° 43'E as per field notes between Secs. 6-7- as per field notes, 40 chains, no trace of $\frac{1}{4}$ corner visible, set stone for temporary corner and continued S 89° 43'E 40 chains and intersected East line of Secs 6, 7. 3.33 chains North of small mound of stones, among them being a small stone having 5 notches on one side but no other marks visible. From testimony of old residents I was convinced that the place was the original corner and proceeded to re-establish the corner by setting a stone 20x10x4 marked with 5 notches on the East and South and also CS on the South face, in an earth mound with pits as per instructions. Returned N 88° 15' W on a straight line between the SE and SW corners of Sec. 6, 40 chains set stone 22x12x5 marked $\frac{1}{4}$ CS on East face for $\frac{1}{4}$ corner between Secs. 6-7 Tp. 5 S R 26 E.W.M.

April 7 1914

Loy M. Turner Co. Surveyor.